

eastern

UTILITIES SERVICES LLC

KEY EQUIPMENT

HORIZONTAL DIRECTIONAL DRILLS

- 2020 Universal 250 x 400 (in production)
- 2020 Vermeer 100 x 140
- 2018 Universal 45/65
- 2014 Ditch Witch JT 30
- 2019 Ditch Witch JT 20
- 2019 McLaughlin MCL Pit Launch
- 2010 Ditch Witch 12/20

RECLAIMER

- Tulsa Rig Iron MCS – 750
- Vermeer Thunderstorm II

VACUUM EXCAVATORS

- 2009 Freightliner 2100 Gallon (Vac Truck)
- 2016 Ditch Witch FX 80 1200 gallon
- 2016 Ditch Witch FX 80 800 gallon
- 2009 Ditch Witch FX 50 500 gallon



Eastern Utilities Services (EUS) specializes in directional drilling and trenchless technology, working with government, municipal, industrial and commercial customers.

COMPANY INFORMATION

Year Established: 2001
 Bondable
 Union Affiliated
 LEED Experience
 BIM Experience

SERVICES PROVIDED

Horizontal Directional Drilling
 Auger Boring
 Utility Construction
 Trenching

SERVICE AREAS

Long Island, New York
 New York City
 Upstate New York
 Connecticut
 New Jersey

PROJECT HIGHLIGHTS

JFK164.020 (PANYNJ) – RECONSTRUCTION OF RUNWAY 13L-31R

Directional Drill - Electrical Conduit (Emergency Installation)
 Distance: 455 LF
 Depth: 20 ft
 Bore Size: 7-inch
 Product: (1) 4-inch HDPE
 Ground Conditions: Mud, Bog, Clay, Ground Water
 Performed With: 2018 Universal 45/65

JFK164.020 (PANYNJ) – RECONSTRUCTION OF RUNWAY 13L-31R

Directional Drill – Communication Conduit (Emergency Installation)
 Distance: 640 LF
 Depth: 20 FT
 Bore Size: 7-inch
 Product: (1) 4-inch HDPE
 Ground Conditions: Mud, Bog, Clay, Ground Water
 Performed With: 2010 JT8020 / 2018 Universal 45/65

JFK164.020 (PANYNJ) – RECONSTRUCTION OF RUNWAY 13L-31R

Directional Drill - Electrical Conduits
 Distance: 1800 LF (6 Bores of 300 LF each)
 Depth: 25 ft
 Bore Size: 28-inch
 Product: (1) 20-inch HDPE
 Ground Conditions: Mud, Bog, Clay, Ground Water
 Performed With: 2010 Ditch Witch JT 8020

BERRY STREET SUB STATION (PSEG)

Directional Drill - Electric Conduit
 Distance: 1500 LF
 Depth: 10 ft
 Bore Size: 18-inch
 Product: (3) 6-inch PVC Conduits
 Ground Conditions: Loam, Sand, Gravel
 Performed With: 2016 Ditch Witch JT 25

BERRY STREET SUB STATION (PSEG)

Directional Drill - Electric Conduit
 Distance: 1500 LF
 Depth: 10 ft
 Bore Size: 18-inch
 Product: (3) 6-inch PVC Conduits
 Ground Conditions: Loam, Sand, Gravel
 Performed With: 2016 Ditch Witch JT 25

GREENPORT (PSEG SUBSTATION)

Directional Drill - Electrical Conduits
 Distance: 1500 LF
 Depth: 10 ft
 Bore Size: 18-inch
 Product: (3) 6-inch PVC Conduits
 Ground Conditions: Sand, Gravel, Large Cobble
 Performed With: 2016 Ditch Witch JT 25



D263860 (NYS DOT) – WALT WHITMAN RD BRIDGE REPLACEMENT

Directional Drill - Water Main
 Distance: 350 LF
 Depth: 25 ft
 Bore Size: 28-inch
 Product: (1) 24-inch HDPE
 Ground Conditions: Sand, Gravel
 Performed With: 2010 Ditch Witch JT 8020

NEW ROCHELLE - NYS THRUWAY

Directional Drill - Electric Conduits
 Distance: 250 LF
 Depth: 20 ft
 Bore Size: 12-inch
 Product: (2) 4-inch PVC Conduits
 Ground Conditions: Bed Rock, Boulder
 Performed With: 2016 Ditch Witch JT 25

BELMONT SUBSTATION (PSEG)

Directional Drill – Electrical Conduit
 Distance: (2) Bores @ 860 LF each
 Depth: 10 FT / 20 FT
 Bore Size: 24-inch
 Product: (3) 6-inch HDPE (2) 4-inch HDPE
 Ground Conditions: Mud, Bog, Clay, Ground Water
 Performed With: 2010 JT8020 / 2018 Universal 45/65